

EXAMPLE ONLY

Erosion and sediment control plan

Legend			
	Property boundary		Diversion drain/bank
	Dwelling site		Stabilised entry/exit pad
	Sediment fence		Level spreader
			Entry/exit bund
			Contour line

Notes:

- All erosion and sediment control structures to be inspected each working day and maintained in good working order.
- All ground cover vegetation outside the immediate building area to be preserved during the building phase.
- All erosion and sediment control measures to be installed prior to commencement of major earthworks.
- Stockpiles of clayey material to be covered with impervious sheet.
- Roof water downpipes to be connected to the permanent underground stormwater drainage system as soon as practical after roof is laid.

